

Grant Agreement 700359





PEM Electrolyser for operation with off-grid Renewable Installations. ELY4OFF Project



Pedro Casero

Project Coordinator Innovation Area Manager (FHa)

Emden 12 February 2019











WHO ARE WE?



Fundación Hidrógeno Aragón

- It is a **private**, **non-profit** organization, created to promote the use of hydrogen as an energy vector.
- Promoted by the Government of Aragon it was founded in 2003 with the support of the administration, industry and the main society actors from different sectors of activity.
- **70 members** of key importance for the Aragonese economy





Installations

- Main building: 1200 m², with offices, labs and warehouse.
- Integrated in the ITHER project, which is a demonstration project with a renewable energy infrastructure based on a wind farm 635 kW and a 100 kW photovoltaic system with different technologies linked to a hydrogen production facility compression (up to 350 bar) and dispensing hydrogen.





Areas of work



Research & Development



Innovation



Consultancy and training



Business development

Background on Fuel Cell & H₂







Making hydrogen affordable to sustainably operate Everywhere in European cities





BIG HIT



Building Innovative Green Hydrogen Systems in Isolated Territories





DEMO4GRID



Demonstration of 4 MW Pressurized Alkaline Electrolyser for Grid Balancing Services





QualyGridS



Standarized qualifying tests of electrolysers for grid services





HYLAW



Identification of legal rules and administrative processes applicable to Fuel Cell and Hydrogen technologies'





HYTECHCYCLING



New technologies and strategies for fuel cells and hydrogen technologies in the phase of recycling and





ELY40FF



PEM ElectroLYsers FOR operation with OFFgrid renewable installations





ELYNTEGRATION



Grid Integrated Multi Megawatt High Pressure Alkaline Electrolysers for Energy Applications






ELYGRID



Improvements to Integrate
High Pressure Alkaline
Electrolysers for Electricity/H2
production from Renewable









SUMMARY





Purpose: the **development** and **demonstration** of an autonomous **off-grid** electrolysis system linked to **renewable energy sources**.

The *PEMWE* (Polymer Electrolyte Membrane Water Electrolyser) industrial prototype (50 kW) will be directly linked to track the solar photovoltaic power source producing over 1.5 tonnes of hydrogen per year and ensuring cold start and rapid response to changes

The *demonstration* period in a relevant environment (TRL 6) will last **8 months** and will take place in Huesca, Spain.

Grant number	700359
Application area	H2020 Energy
Start date	01/04/2016
End date	31/03/2019
Total Budget (€)	2.315.217,50€





































Emden, Germany Cloudly the following days



Rainfall: 0%

Temperatura


Humidty: 85%

Wind: 14 km/h

Precipitaciones

Viento

6	5	4	3	4	3	3	4
15:00	18:00	21:00	0:00	3:00	6:00	9:00	12:00
mar.	mié.	jue.	vie.	sáb.	dom.	lun.	mar.
6° 3°	6° 5°	8° 4°	8° 7°	9° 5°	8° 4°	6° 2°	6° 2°






























DEMO SITE (Huesca)













DEMO SITE (Huesca)













DCDC CONVERTERS








- ✓ To adapt the voltage produced by the PV field to the required voltage of the stack (with MPPT)
- ✓ Capable of following RES variability quickly
- ✓ Novel electronic structure
- ✓ Effiencies > 92% in all conditions
- **✓ 13 units** (4,8 kW)








DCDC CONVERTERS








PV field output: 450 – 800 V

Stack requirements: 110 – 160 V













DCDC CONVERTERS













HGAS PEM ELECTROLYSER







- ✓ Promising results, but an MEA could not be developed in time -> a commercial MEA was tested
- ✓ Optimization of **BoP consumption** (variable pump, thermal insulation, ...)
- ✓ Non-typical FAT: no rectifier at factory -> on site after DCDC integration
- ✓ Final tests done 5-8 Feb 19 were successful: good dynamic response
- ✓ Many control modifications due to off-grid







HYBRID STORAGE SYSTEM (I)













HYBRID STORAGE SYSTEM (2)












HYBRID STORAGE SYSTEM











COMMUNICATION AND CONTROL







Idle


The PEMWE's BOP <u>essential consumptions</u> are covered (PLC, anti-freezing system) as well as the PLCs in the microgrid. **24/7**


Standby

The PEMWE's BOP <u>non essential consumptions</u> are covered, as well as those covered in the Idle status

Generation

The PEMWE's stack is **generating hydrogen**, being the BOP consumptions also covered.







CURRENT STATUS






- ✓ Integration of the components and commissioning is taking more time than expected -> current delay of 6 months.
- ✓ Successful tests last week -> demo period to start in March 19 (permits obtained, official documentation in elaboration)
- ✓ Project ends in March -> an extension has been requested.
- ✓ Other on-going activities: LCA, cost analysis, recommendations to overcome regulatory barriers, exploitation plan, ...
- ✓ Business cases assessed (CEA): re-electrification, grid injection, mobility











FINAL MESSAGES






High System Efficiency

through improved PEMWE and direct DC/DC

Reliable

Hybrid Storage System with enhanced autonomy















This project has received funding from the Fuel Cells and Hydrogen 2 Joint Undertaking under grant agreement No (700359). This Joint Undertaking receives support from the European Union's Horizon 2020 research and innovation programme, Hydrogen Europe and Hydrogen Europe research.

Many tanks for your attention,

Pedro Casero

Project Coordinator

pcasero@hidrogenoaragon.org